<u>Item #8</u>:
Proposal For Temporary Repairs To RPC Road Bridge

CROSSROAD CONSTRUCTION, INC.

1N725 Swift Road, Lombard, IL 60148 * Phone (630) 847-9400 * Fax (630) 627-9601

SENT VIA EMAIL

PROPOSAL

Friday, August 21, 2015

Mr. Geoff Perry
Civil Tech Engineering, Inc.
450 E Devon Ave #300
Itasca, IL 60143
Phone (847) 821-6231

Project: Robert Parker Coffin Bridge

We are pleased to provide the following quotation per site inspection 08/21/2015.

Scope of Work

Provide all labor and material to:

• Mobilization for one or all of the recommend repair tasks will be $5000.00.	**$5,000.00**
• Furnish and install a replacement rod connection system. This system would consist of a 2 x 2 x 3/16" galvanized angle. One angle per plank running the full length of the plank. One 5/8" lag bolt will be provided for each gap between I-beam runners (approx. 10 lags per angle/plank).	**$7,000.00**
• Replacement of missing angle on east side abutment. Angle to be welded full penetration vertical and horizontal surfaces to match existing angle.	**$495.00**
• Support east end of runners connecting to the bearing seat. Combination of shims and tie downs into bearing seat or abutment will be required.	**$7,000.00**
• Tighten turn buckles to a pre determined torque values as specified by Civil Tech. Remove coating to facilitate tightening to the specified torque. Re coat all bare steel to maintain corrosion protection.	**$495.00**
Grand Total:	**$19,990.00**

Special Conditions

All work performed under this contract is done in compliance with all applicable State and Federal Laws, Rules and Regulations.
No changes, extensions, or other modifications shall be effective unless confirmed in writing and signed by an authorized agent of both parties.
The above work will require a bridge shut down of approximately 5 working days providing satisfactory weather conditions.
Lead time for mobilization may be up to 21 days after acceptance of proposal.
Any insurance requirements over and above our standard available insurance will be an additional charge.
No permits or other fees have been included in this quote.
Price valid for 30 days from the date of this proposal.
Terms: Net 30.

Geoff Perry
Civil Tech Engineering, Inc.

Salvatore Gruttadauro
Crossroad Construction, Inc.