



ITEM #4: For the ARCHITECTURAL COMMISSION; on MONDAY, August 18th @ 7:00 P.M.

REQUEST: Consideration of a request for signage for Sherwin Williams, "Building C"; 4194 Route 83; Unit C and within the Sunset Grove Development, submitted by VanBruggen Signs.

HISTORY/STAFF REVIEW:

HISTORY:

The property is located on the southeast corner of Route 83 and Aptakisic Road. The property consists of 16 +/- acres of land area. The property is presently zoned HR-1 Commercial District & OS-P with a special use permit for a Planned Unit Development. The Village Board granted final PUD plan & plat approval in November 2008 (Ord. # 2008-O-27).

"Building C" is one the last two structures to be built in the Sunset Grove Development and received AC review and approval in September of 2013. At that time it was noted individual signage requests would be brought to the back to the Commission as received for further consideration.

Sherwin Williams is the first and "anchor" tenant for "Building C"

STAFF REVIEW:

The property in question is located at 4194 Route 83 and is located in Building "C" north of the Sunset Food Building in the Sunset Grove Development and fronting on Aptakisic Road.

Per the final PUD approval ordinance (Ord. 2008-O-27) signage was approved as follows;

- A. **Signage.** All signage for the Proposed Development shall be located and installed in accordance with the Final PUD Plans. No more than 70% of the "Designated Zone for Placement of Signage and Graphics" depicted on the building elevations included within the Final Signage Plan may be occupied by tenant signage. "Alternate Sign 'A'", as depicted on the Final PUD Plans, may contain any of the following combinations of "Top Panels" (20 square feet of signage) and "Other Panels" (7.6 square feet of signage), as such panels are depicted on the Final Signage Plan: (i) four (4) Top Panels and zero (0) Other Panels; (ii) three (3) Top Panels and two (2) Other Panels; (iii) two (2) Top Panels and four (4) other Panels; (iv) one (1) Top Panel and six (6) Other Panels; or (v) zero (0) Top Panels and eight (8) Other Panels. The size, color, copy, and materials of all tenant signage including, but not limited to, the window treatments of the drug store (Building "D"), shall be subject to Architectural Commission review and approval. Any approved signage may be replaced by signage in the same location and of equivalent or smaller size, subject to Architectural Commission review and approval. Any other additional or replacement signage must undergo full review for a sign permit and receive Architectural Commission approval in accordance with the Village Code. **Electronic sign boards, neon signage, flashing signage, and internally illuminated signage shall be prohibited.**

A copy of the approved elevation for "Building C" is attached. As signage relates to this portion of building, the "Sherwin Williams" signage, as proposed, is in the "Designated Zone for Placement of Signage and Graphics" as indicated on the approved PUD plans.

Per the building plans submitted for approval the "Designated Zone for Placement of Signage and Graphics" is as follows;

North Elevation – 1 sign;
Placement Zone Dimensions: 12' x 4.0' = 48 sq. ft. x .70 = 33.6 sq. foot of signage

East Elevation – 1 sign;
Placement Zone Dimensions: 41' x 4.0' = 164 sq. ft. x .70 = 114.8 sq. foot of signage

PROPOSED SIGNAGE

Petitioner is proposing two wall signs on the north and east facades of “Building B” in the locations approved as the “Designated Zone for Placement of Signage and Graphics”. This is consistent with the final PUD approvals. Both signs are identical in terms of square footage.

The size of the proposed signage is as follows;

	<u>Proposed Sq. Footage</u>	<u>Sq. Footage Allowed per PUD Approval</u>
North Elevation:	10.75' x 3.6' (37.8 sq. ft.)	33.6 Sq. ft.
East Elevation:	10.75' x 3.6' (37.8 sq. ft.)	114.8 Sq. ft.

The proposed signage is on the east elevation is within the allowable square footage for such signage as allowed by the PUD approval ordinance, however the square footage of the signage on the north elevation appears to exceed the maximum allowable square footage by 4.2 square feet. Per the Village Code the square footage of signage is calculated as follows;

Sign Measurement: Unless otherwise expressly provided to the contrary in these regulations, the term "sign area" shall include the gross surface area of each sign with a single continuous perimeter enclosing the extreme limits of the sign and in no case passing through or between any adjacent elements of the sign. Such a perimeter shall not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display.

A sign placard will also be placed on pylon sign number 2 on the Route 83 frontage. This sign will be consistent with the other placards on the pylon sign and is permissible at this location.

MATERIALS & ILLUMINATION

The signage is proposed to be channel letters in white acrylic with a blue backer and the “Cover the Earth” logo in red white & blue. Letters will be mounted to the building. Signs are proposed to be illuminated with backlit LED lighting consistent with other illumination within the development.

ARCHITECTURAL COMMISSION DECISION:

Signage as proposed is permissible under the approved PUD Ordinance except for the size of the sign on the north elevation which is 4.2 square feet larger than permissible.

It is suggested that consistency as well as the overall character of the development be considered with regard to individual signage requests.

FOR OFFICE USE ONLY:	
ARB Received:	
ARB Reviewed:	
ARB Approved:	
Village Bd. Approved:	



VILLAGE OF
LONG GROVE

SIGN PERMIT
ARCHITECTURAL BOARD APPLICATION

FOR OFFICE USE ONLY:		
Date Received:		
Permit No.:		
Date Issued:		
Township:		
Sec:	T:	R:
PIN No.:		
Zoning:		

RECEIVED

AUG 05 2014

VILLAGE OF LONG GROVE

BUSINESS NAME: SHERWIN WILLIAMS	BUS. PHONE #:
BUSINESS ADDRESS: 4194 IL RT 83 UNIT A	
BUSINESS OWNER'S NAME: SEAN KOTENTAUER	ALTERNATE PH. #: (440) 846-4105

TYPE OF SIGN(S) FOR WHICH YOU ARE APPLYING:	(2) ILLUMINATED WALL SIGNS / (1) TENANT PORTION OF EXISTING SIGN
---	--

The Architectural Board meets every third (3rd) Monday of the month at 7:00pm in the Village Hall. The applicant (or representative) must be present. Please prepare and submit six (6) sets of all of the following information two weeks prior to the meeting:

- THIS FULLY COMPLETED APPLICATION SIGNED BY BOTH THE PETITIONER AND THE PROPERTY OWNER
- REGARDING THE POSITION OR LOCATION OF PROPOSED SIGN ON THE BUILDING OR PROPERTY:
 - PROVIDE SITE PLAN
 - PROVIDE PHOTOGRAPH OF THE LOCATION ON THE PROPERTY OR BUILDING WHERE THE SIGN WOULD BE INSTALLED
 - SQUARE FOOTAGE OF COMMERCIAL SPACE FOR WHICH SIGN IS BEING INSTALLED:

3,217	sq. ft.
-------	---------
- PROVIDE A DETAILED DRAWING (TO SCALE) OF THE PROPOSED SIGN, INCLUDING:
 - DIMENSIONS
 - SAMPLE OF COLORS ON SIGN
 - LETTER STYLE TO BE USED
 - SAMPLE OF ANY UNUSUAL MATERIAL TO BE USED ON THE SIGN

Should the sign be completed prior to the architectural board's approval (this is not encouraged), the sign itself, or a photograph of the sign, shall be presented at the Architectural Board meeting.

SIGN CONTRACTOR:

NAME: VAN BRUGGEN SIGNS	PHONE #: 708-448-0826
ADDRESS: 13401 SOUTHWEST HWY. ORLANDO PK, IL. 60462	

The property owner's signature is required below before any sign application may be processed. The property owner's signature is confirmation that he/she has read and understands the regulations governing the erection of signs in the Village of Long Grove and further approves the erection of the above-described sign on his/her property.

Jack Sunm
PROPERTY OWNER(S) SIGNATURE(S)


SUNSET GROVE, LLC
PROPERTY OWNER(S) PRINTED NAME(S)

Sean Kotentauer
BUSINESS OWNER(S) SIGNATURE(S)


(See the reverse side for maximum sign dimensions and fee schedule.)

3110 RFD • LONG GROVE, ILLINOIS 60047-9635
(847) 634-9440 • FAX (847) 634-9408

SQUARE FOOTAGE • Logo: 5.58 sq. ft. Letters: 24.07 sq. ft. TOTAL: 29.65 sq. ft. BLUE ALUMINUM BACKER 4'-0" x 11'-7"



REDUCED 25% Register Mark
White vinyl on the Blue Backer



4'-0" x 11'-7" ALUMINUM BACKER PANELS
BACKERS to MATCH PMS# 293 BLUE
(SATIN FINISH)
ROUNDED CORNERS on EACH END

38" COVER THE EARTH CONTOUR LOGO SIGN:
PMS# 293 BLUE, "SPECIAL COLOR RED" plus WHITE - SCREENED
LED POINT 3 WHITE - 6300K

LETTERS: LED POINT 3 WHITE - 6300K - 9 per foot (1 ROW)
ILLUMINATED WHITE ACRYLIC #7328 PIGMENTED FACES
WHITE VINYL REGISTER MARK ON THE BLUE BACKER
TRIM CAP - 1 INCH METALLIC BRONZE IS GLUED TO ACRYLIC FACES


RETURNS and BACKS are FABRICATED
of ALUMINUM, FULLY
WELDED - PRIMED and PAINTED SHUTTER BROWN.
RACEWAY CENTERED
(8" HIGH x 8" DEEP with CONCEALED
MOUNTING BRACKETS)
PAINTED to MATCH PMS# 293 BLUE




TENANT PANEL SIZE to be DETERMINED

EAST ELEVATION:

PLEASE NOTE: PLACEMENT and SIZE of the LETTERS on the BUILDING
are APPROXIMATE and for SKETCH PURPOSE ONLY



EAST ELEVATION



NORTH ELEVATION

Dualite
Dualite Sales & Service, Inc.
One Dualite Lane
Williamsburg, Ohio 45176


FILE#13-10-55HER01-GSP3
Scale: 1/4" = 1'-0"
Date: 7-29-2014 rev

CB
Customer Approval
or Comments:

This design is exclusive property of Dualite Sales & Service, Inc. • 1 Dualite Lane • Williamsburg, OH 45176 • Copyright 2014 Dualite Sales & Service, Inc.
All Rights Reserved. Reproduction of this proprietary work without the permission of Dualite Sales & Service, Inc. will subject the user to liability under the copyright statutes of the United States.

EXHIBIT B-PLOT PLAN

WALL SIGNS ON THE
NORTH AND EAST ELEVATIONS




LONG GROVE, ILLINOIS

09/13/2013


M:\REALESTATE\DWGS\WORK\E13_FILES\E13031\E13031.dwg

© The Sherwin Williams Company 01/01/2013




Common Monument
Size: 48' x 5'
Area: 240 sf

Area: 300 sf



Private Monument 2
Size: 6'-8" x 8"
Area: 108 sf



Pylon 2
Size: 15' x 10'
Area: 300 sf



Private Monument 1
Size: 6'-8" x 8"
Area: 108 sf



Pylon 1
Size: 15' x 10'
Area: 300 sf

MONUMENT SIGN AREA SUMMARY	
PUD AREA:	1,440sf
PROPOSED AREA:	1,356sf

